

Construction Notification



Contact Information:

Renee McClure
Manager, Community & Customer Management
One MetroTech Center, Brooklyn, NY 11201
(929) 324-4390
Renee.McClure@nationalgrid.com

Project Manager:
Christopher Zimmermann
Engineer
347-461-3392
Christopher.Zimmermann@nationalgrid.com

Notification Details

February 8, 2021

In the coming weeks, National Grid has planned construction in your district and this notification will provide information on the project. This work is required to improve the reliability of our gas system. If you seek additional information, please reference the following:

Construction due to:	Install Main	Borough:	Brooklyn
Reference Number:	T102375736	Billing Unit:	29
		Community Board:	8

Construction Details

Scope:	Install Main	Typical Trench Width:	3'	Approx. Duration:	90 Days
---------------	--------------	------------------------------	----	--------------------------	---------

Locations

On Street	Cross Street	Cross Street
Pacific St	Schenectady Ave	Utica Ave

What to expect during construction

- Typically, work performed by National Grid will begin with the installation of new gas pipe either in the street or sidewalk. The excavation required will be backfilled at the end of each day. Steel plates will be used to cover any excavations left open to allow vehicular traffic and provide access to driveways, steps, and walkways.
- The entire work area will be kept clean and orderly. Attempts will be made to keep noise, dust, and debris to a minimum. All material required on site will be stored neatly in designated areas.
- All or part of your gas service may have to be replaced. In order to complete this work, we must gain access to your home at the point where the service enters the building (basement, crawlspace, etc.). If this is the case, you will be contacted by a National Grid representative to make an appointment.

Restoration

- Some excavations may need to remain open until all gas services have been transferred, at which point the old main will be retired and the openings will be backfilled.
- All street and sidewalk surfaces affected by the construction will be repaved to ensure a smooth surface. Temporary asphalt pavement will be used until all National Grid work is complete and permanent restoration can be performed.
- Concrete openings should be restored within 21 days with the exception of work done in mid-winter. Some delays may occur due to inclement weather or when the temperature is too cold to pour concrete.