





Brooklyn

Fourth Quarter 2021

Replacement of Combined Sewers, Bulkheading of Existing Sewers and Water Main Replacement in Park Place.

Brooklyn

The NYC Department of Design and Construction (NYCDDC) is upgrading the infrastructure within Prospect Heights, Brooklyn to improve water drainage and quality. The DDC will install replacements of distribution water mains, install combined sewers, and restore the trenches where the work was performed. The project involves the replacement and/or reconstruction of combined sewers, manholes, chambers, catch basins, distribution water mains and hydrants. This project includes final restoration for all water and sewer trenches, resurfacing with a 2" overlay of asphaltic concrete wearing course, and installation of new streetlights and traffic lights at the intersection of Carlton Avenue and Park Place.

Current Locations for Work Operations:

- Replacement of existing watermains:
 - Vanderbilt Avenue between Park Place and Sterling Place
 - Underhill Avenue between Park Place and Sterling Place

Upcoming Locations for Work Operations:

- Installation of combined sewers:
 - Park Place between Flatbush Avenue and Vanderbilt Avenue
 - Park Avenue between Vanderbilt Avenue Underhill Avenue
 - o Installation of Sewer Chamber:
 - Intersection of Carlton Avenue and Park Place

Completed Work Operations to Date:

Replacement of Water Main:


- Replacement of 250 linear feet of DIP Watermain
- Replacement of four (4) 8" gate valves
- Replacement of four (4) 12" gate valves
- Replacement of four (4) fire hydrants
- Replacement of 20" water main on Underhill between Park Place and Sterling
- Replacement of 8" water main on Underhill between Park Place and Sterling
- Replacement of 12" water main on Vanderbilt between Park Place and Sterling

Community Impacts

During construction hours, you can expect the following:

- Increased levels of dust, noise, and heavy equipment.
- Vehicular travel lane closures will be required, as well as detours. Warning signs will be posted in advance.
- Parking and driveway/loading dock restrictions. Signs will be posted within the affected areas. Emergency vehicle access and pedestrian access to sidewalk and buildings will be maintained at all times.

Project # SEK002386



The neighborhood we are working on is Prospect Heights

Water Service Interruptions

During the project, there will be service interruptions. To facilitate water main replacement, the existing water service must be shut off by closing the valves at either end of the section. Advanced notice will be given for all planned interruptions. Water service will be restored at the end the workday

Newsletter Distribution

Construction Newsletters for this project are distributed regularly within the project area and to Brooklyn Community Board 8

Special Needs

Individuals with special needs who may be uniquely impacted by this project should contact the project's Community Construction Liaison, as soon as possible, to make them aware of your situation. DDC will work with you to try to minimize the inconvenience as much as possible.

Property Damage

You are advised to inform the DDC or the Contractor of any property damage that may have occurred due to this project. If the contractor fails to respond within 10 days, you should inform the DDC Borough Director in writing. If you intend to file a claim you must do so within 90 days of the occurrence with the New York City Comptroller's Office.

Community Construction Liaison (CCL)

The DDC has assigned **Danilo Mikhaylov** as the Community Construction Liaison (CCL) for this project. Please contact Mr. Mikhaylov for any project related inquiries/concerns you may have:

Phone: 516.464.0614 Email: Parkplccl@gmail.com

Field Office: 250 6th Street, Brooklyn, NY 11215